

## 4.5 – REBAR

Rebar estimating varies from wall to wall depending on factors such as height, vertical loading, horizontal loading, backfill heights, etc.

**NOTE:** Each Brick Ledge will require six stirrups to tie the horizontal rebar in the corbel to the horizontal rebar in the interior of the form.